

**जाहिर सूचना**

विषय :- प्राधिकरणाच्या नवीन प्रशासकीय इमारतीमधील किरकोळ दुरुस्ती, पेटिंग इ. बाबीचे अंदाजपत्रक बनवणेसाठी दरपत्रे मागवणेबाबत.

पिंपरी चिंचवड नवनगरविकास प्राधिकरणाच्या नवीन प्रशासकीय इमारतीमधील किरकोळ दुरुस्तीची कामे, पेटिंग इ. बाबीचे अंदाजपत्रक तयार करणेसाठी सदर प्रकारची कामे करणारे कंत्राटदार / पुरवठादार यांचेकडून दरपत्रके मागविण्यात येत आहे.

बाबीचा तपशील पुढीलप्रमाणे:

Sr.No	Description of work	Unit	Rate /Unit
1	providing and fixing heavy duty inter blocked concrete paving block of 100 mm thickness of having strenght of 500 kg sqmt of approved quality and shape of 1:6 cement mortar including cement float striking joint curing and cleaning etc. complete	Sqm	
2	Staircase well reailing : 50 mm dia 5.5 304 16 gauge pipe top rail with 3 nos horizontal rails of 12 dia 5.5 304 rod with vertical supports as per drawing of 50mm dia 5.5 304 16 gauge pipe in combination with 12 dia 5.5 rods qroued to RCC pardi / floor with 90 dia 3 mm thick 5.5 304 plate with chamfered.	Sqm	
3	providing and fixing of powder coated alluminium horizontal fixed lower main frame made for 80X38X1.5 mm thick hollow rectangular tube fixing on it 100X25X1.5 mm thick aerofil type fixed louverd with cleats and screws fixing the main frame to the wall column with wood screws all complete	Sqm	
4	providing and fixing modular false ceilling of mineral board on GI runner of Arm strong make model optra pebble microlook tile size 600X600X15mm grid of suprafine 15mm edge including all leadsand lift complete.	Sqm	
5	providing and fixing gypsum board on GI frame 22 guage horizontally in 600X600 grid with proper filling of joint in the line and level etc including all leads and lifts complete .	Sqm	
6	providing and fixing full height glass block partitions using imported make of glass block of size 200X200X80 mm with jointing compound adhesive mixed white cement and The joint shall be finished neatly as per manufacture specification Rate shall be inclusive of providing ply with metalic laminate band around, hardware etc. as show in drawing the partition shall be irrected perfectly line and level as per profile shape additional specifications selection & final material approval as directed by engg in charge.	Sqm	

7	Vertical blinds : Providing & Fixing vertical blinds with 100 mm & 89 mm wide imported superior polyester base fabric vanes with scotch guard application as per approved sample make of vista leveler or equivalent and the range of louver shall be in select and class is the vertical blind shall have a head rail of extruded anodized high strength aluminum alloy shall be 25mm X 50mm high or equivalent with wall thickness of 1.2 mm or equivalent end control units consists of reduction	Sqm	
8	Display soft Board: Providing & fixing display soft Board providing and fixing in position 12 mm height soft board paneling on existing wall including fabric cover with wooden beading size (25 X 12mm) finished with 3 coats of melamine polish of approved shade etc. complete size of board as per drawing.	Sqm	
9	Pin-up board : Supplying & fixing in position pin up boards fabricated with 6 mm ply covered with 12 mm soft board padding and up to holdtered with fabric costing rs 150/- per mtr the edge of soft wood to have teak wood moulding melamine polished additional specification as directed by Engineer in charge.	Sqm	
10	Fire rated encasement : Providing & applying two layer of 15 mm thick gyproc fire line boards as per drawing to increase of MS structural member which are expose to internal side of building which directly expose to heat of a flame Including necessary fitting like screw gypsteel ultra steel section like steel fire line board necessary scaffolding.	Sqm	
11	Lighting : Satellite reflecto parachute with looping loop out box 618 dia height K – Lite make no.6674.	No	
12	providing and fixing 75 mm thick gypsum boards partitions,1200 mm wide gypsum plaster board (conforming IS2095-1982) on both sides and ceiling channels at 600 mm center floor channels fixed to concrete sole plate and ceiling channels fixed to concrete soffit by nylon row plugs @ 600 cm c/c and providing and fixing 50 mm resin bonded fiber glass wool insulation 48kg/ cum density providing & fixing of edge beads, corner protection angle bead fixing making 10 mm wide groove using alluminium angle p/f laminate in group 100 mm high vitrified tile skirting fixed on marine plywood box using low voc adhesive as per drawing additional specification and as directed by engineer in charge	Sqm	
13	providing STAGE SCAFFOLD using steel scaffold pipe frames made of 40 mm dia MS pipe & bracing with scaffolding boards including hire charges for MS pipe frames scaffolds boards etc. and cost & conveyance of all other consumable accessories taxes etc. complete for finish item of work plan area.	Sqm	
14	Removing glass shutter	Sqm	
15	Removing corrosin of metal column.	Sqm	
16	Providing zink oxide anti corrosim paint to column.	Sqm	

17	Removing of film glass and cleaning of glass panelles with fitting	Sqm	
18	Providing & fixing floor spring to woodan doors.	Sqm	
19	Providing & fixing door locks to woodan doors.	Sqm	
20	Providing & fixing nameboards on 10 mm alluminium plate in daoming reflective material.	Sqm	
21	Cleaning of louvers walkway.	Sqm	
22	Providing & fixing metal fall ceilling in walkway protion.	Sqm	
23	Providing water proofing on canteen poly corbonate shade.	Sqm	
24	Providing super elevation at turning of Road work.	Sqm	
25	Removing of grass paver.	Sqm	
26	Removing of existing pvc pipe.	Sqm	

याकरीता अटी व शर्ती खालीलप्रमाणे..

- १) आपले दर संस्था /शॉप च्या लेटर हेडवरती असणे आवश्यक आहे.
- २) उपरोक्त दर हा GST व्यतिरीक्त Quote करावा.
- ३) आपले दरपत्रके दि.२३/०७/२०१८ पूर्वी कार्यालयात पोहच करावेत.
- ४) सदरचे दर हे फक्त अंदाजपत्रक बनविणेसाठी वापरण्यात येणार आहेत.

सही/---  
कार्यकारी अभियंता  
अभियांत्रिकी विभाग – ब