

**जाहिर सूचना**

विषय :- प्राधिकरणाच्या नवीन प्रशासकीय इमारतीमधील किरकोळ दुरुस्ती, पेटिंग इ. बाबीचे अंदाजपत्रक बनवणेसाठी दरपत्रे मागवणेबाबत.

पिंपरी चिंचवड नवनगरविकास प्राधिकरणाच्या नवीन प्रशासकीय इमारतीमधील किरकोळ दुरुस्तीची कामे, पेटिंग इ. बाबीचे अंदाजपत्रक तयार करणेसाठी सदर प्रकारची कामे करणारे कंत्राटदार / पुरवठादार यांचेकडून दरपत्रके मागविण्यात येत आहे.

बाबीचा तपशील पुढीलप्रमाणे:

Sr.No	Description of work	Unit	Rate /Unit
1	Providing & applying acrylics scratch finish texture wall finish of 1.5 mm to 2.00 mm thickness on bed of plaster externally to get permanent finish flexibility & elasticity with excellent water spec. as directed by Engineer in charge.	Sqm	
2	Providing and laying verified tiles 900X900X8 mm thick for flooring in required position laid on bed of 1:6 cm including cement float filling joints with neat cement slurry /grout curing polishing and cleaning complete	Sqm	
3	providing and laying 20mm thick granite for flooring with leather finish as show in drawing in required position laid on bed of 1:6 cm including cement float filling joint with neat cement slurrycuring polishing and cleaning complete	Sqm	
4	providing and fixing door frame jamb in granite as show in drawing and details in cm 1:4 including cement float filling joint with slurry curing polishing and cleaning etc complete	Sqm	
5	providing and laying polished machine cut black granite slab 20 mm thick for sills on a bed of 1:4 cement mortar including cement float filling joint with neat cement slurry curing polishing and cleaning complete	Sqm	
6	providing and fixing heavy duty inter blocked concrete paving block of 100 mm thickness of having strenght of 500 kg sqmt of approved quality and shape of 1:6 cement mortar including cement float striking joint curing and cleaning etc. complete	Sqm	
7	Providing & applying valvet finish to internal surface of approved colour and shade to old new surface in two coats including scaffolding preparing the surface.	Sqm	

8	Providing & fixing solid core certified wood flush door 38mm thick with approved face laminate sheet 1mm thick on both face with etched glass panel as per drawing or as directed including all necessary beads moulding and lipping in BTC stainless fixtures locks and fastening including floor springs 80 kg minimum bearing and stainless steel handle 300 mm height 22 mm diameter on both sides providing melamine polished to all lippings beads and moulding	Sqm	
9	Staircase well railing : 50 mm dia 5.5 304 16 gauge pipe top rail with 3 nos horizontal rails of 12 dia 5.5 304 rod with vertical supports as per drawing of 50mm dia 5.5 304 16 gauge pipe in combination with 12 dia 5.5 rods grouted to RCC pardi / floor with 90 dia 3 mm thick 5.5 304 plate with chamfered.	Sqm	
10	providing and applying weather guard of approved colour and shades to old and new surface in two coats including scaffolding preparing the surface (excluding the primer coat) complete.	Sqm	
11	providing ,supporting,culverting and preserving for one year acclimatised plants (50 sqm) specification as directed by engineer in charge	Sqm	
12	providing and fixing of powder coated aluminium horizontal fixed lower main frame made for 80X38X1.5 mm thick hollow rectangular tube fixing on it 100X25X1.5 mm thick aerofil type fixed louvers with cleats and screws fixing the main frame to the wall column with wood screws all complete	Sqm	
13	Providing & fixing of laminated glass glazed skylight. Frame made in grid pattern from M.S. epoxy painted rectangular tube of appropriate size for both vertical & horizontal section welded to each other frame fixed to the slab/ soffit with M.S. base plate and anchor fastness skylight section made from 2 .5 mm thick silver anodised aluminium skylight section fix to the M.S. structure with screws. fixing over it laminated glass comprising of 6mm clear H.S. glass + 0.76 mm PVB lamination + 6 mm clear H.S. glass with EPDM gasket & silver anodised aluminium pressure plate sealing the periphery with weather silicone sealant complete	Sqm	
14	providing and fixing modular false ceiling of mineral board on GI runner of Arm strong make model optra pebble microlook tile size 600X600X15mm grid of suprafine 15mm edge including all leads and lift complete.	Sqm	
15	providing and fixing gypsum board on GI frame 22 gauge horizontally in 600X600 grid with proper filling of joint in the line and level etc including all leads and lifts complete .	Sqm	

16	providing and fixing full height glass block partitions using imported make of glass block of size 200X200X80 mm with jointing compound adhesive mixed white cement and The joint shall be finished neatly as per manufacture specification Rate shall be inclusive of providing ply with metallic laminate band around, hardware etc. as show in drawing the partition shall be irrected perfectly line and level as per profile shape additional specifications selection & final material approval as directed by engg in charge.	Sqm	
17	Vertical blinds : Providing & Fixing vertial blinds with 100 mm & 89 mm wide imported superior polyester base fabric vanes with scotch quard application as per approved sample make of vista leveler or equivalent and the range of louver shall be in select and class is the vertical blind shall have a head rail of extruded anodized high strength aluminum alloy shall be 25mm X 50mm high or equirvalent with wall thickness of 1.2 mm or equivalent end control units consists of reduction	Sqm	
18	Toilet mirror : Providing & fixing toilet mirror (of size 1450 mm X D 600 mm) on wall with 6mm belgion glass mirror with beveled edge fixed over wall with cp costud the molding/ camper of mirror complete as directed by Engineer in charge.	No	
19	Towel Rod: providing and fixing towel rod 24"round chrome finish as per the instruction of architect / engineer in charge (make jaguar catalogue continental series -1111)	No	
20	SS Dust bin : Supply & fixing ss chrome finish perforated Dustbins as per work Station area meeting rooms record room as per the instruction of Architect / Engineer In Charge. Size : 300 mm dia x 450 mm height	No	
21	Display soft Board: Providing & fixing display soft Board providing and fixing in position 12 mm height soft board paneling on existing wall including fabric cover with wooden beading size (25 X 12mm) finished with 3 coats of melamine polish of approved shade etc. complete size of board as per drawing.	Sqm	
22	Pin-up board : Supplying & fixing in position pin up boards fabricated with 6 mm ply covered with 12 mm soft board padding and up to holdtered with fabric costing rs 150/- per mtr the edge of soft wood to have teak wood moulding melamine polished additional specification as directed by Engineer in charge.	Sqm	
23	Oil paint: Providing & applying valvet finish to internal surface of approved colour and shade to old & new surface in two coat including scaffolding preparing the surface.	Sqm	
24	Fire rated paint : Providing & applying three coats of	Sqm	

	intumescant foam coating kem fire – 206 on surface of MS structural member which are exposed internal side of building which directly exposed to heat of a flame of fire for acting to insulate the substrate from the fire source for delay the ignition of flammable substrate for internal use to provide fire resistance for 3 to 4 hours including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wood scraper & sand paper scaffolding.		
25	Fire rated encasement : Providing & applying two layers of 15 mm thick Gyproc fire line boards as per drawing to increase the fire resistance of MS structural member which are exposed to the internal side of building which directly expose to heat of a flame. Including necessary fittings like screws, gypsteel, ultra steel section like steel fire line board, necessary scaffolding.	Sqm	
26	Providing & fixing glass mosaic tiles of approved quality & size for dado and skirting in required positions on plasters of 1:4 cement mortar excluding all specials required like round corner tiles, cup etc. filling joints with white cement slurry, curing and cleaning complete.	Sqm	
27	Lighting : Satellite reflector parachute with looping loop out box 618 dia height K – Lite make no.6674.	No	
28	Providing and fixing 75 mm thick gypsum boards partitions, 1200 mm wide gypsum plaster board (conforming IS 2095-1982) on both sides and ceiling channels at 600 mm center floor channels fixed to concrete sole plate and ceiling channels fixed to concrete soffit by nylon row plugs @ 600 cm c/c and providing and fixing 50 mm resin bonded fiber glass wool insulation 48kg/ cum density providing & fixing of edge beads, corner protection angle bead fixing making 10 mm wide groove using aluminium angle p/f laminate in group 100 mm high vitrified tile skirting fixed on marine plywood box using low voc adhesive as per drawing additional specification and as directed by engineer in charge.	Sqm	
29	Providing STAGE SCAFFOLD using steel scaffold pipe frames made of 40 mm dia MS pipe & bracing with scaffolding boards including hire charges for MS pipe frames scaffolds boards etc. and cost & conveyance of all other consumable accessories taxes etc. complete for finish item of work plan area.	Sqm	
30	Removing glass shutter	Sqm	
31	Removing corrosion of metal column.	Sqm	
32	Providing zinc oxide anti corrosion paint to column.	Sqm	

33	Removing of film glass and cleaning of glass panelles with fitting	Sqm	
34	Providing & fixing floor spring to woodan doors.	Sqm	
35	Providing & fixing door locks to woodan doors.	Sqm	
36	Providing & fixing nameboards on 10 mm alluminium plate in daoming reflective material.	Sqm	
37	Cleaning of louvers walkway.	Sqm	
38	Providing & fixing metal fall ceilling in walkway protion.	Sqm	
39	Providing water proofing on canteen poly corbonate shade.	Sqm	
40	Providing super elevation at turning of Road work.	Sqm	
41	Removing of grass paver.	Sqm	
42	Removing of existing pvc pipe.	Sqm	
43	Providing Resetting of glass doors of HOD cabins with necessary fitting like springs locks etc.	Sqm	
44	Providing Handles to wooden door lock as well as glass doors.	Sqm	
45	Providing & fixing Hand Shower (573) & two way bib cock (5041) ot jaguar make MCH with pvc inlet connection all complete.	Sqm	
46	Providing & fixing flat balck sensor urinal including	Sqm	
	a) flat black sensor urinal of hindware make ( 60007) standard quality of	Sqm	
	b) Necessary brackets & screws etc.	Sqm	
	c) urinal sensor	Sqm	
	d) urinal spreader	Sqm	
	e) urinal waste coupling 1” dia	Sqm	
	f) 1” dia cp bottle trap jaguar (769B – MCH) with extenssion piece cp with all necessary accessories etc all complete.	Sqm	
47	Providing & fixing inlet sypon & outlet sypon for camods	Sqm	
48	Providing & fixing Hindware mate camod seat cover.	Sqm	
49	Providing & fixing battery box to urinal sensor	Sqm	

50	Providing & fixing sensor battery cells.	Sqm	
51	Providing & fixing sensor eye bracket.	Sqm	
52	Providing & fixing solvonet bracket of hindware.	Sqm	

याकरीता अटी व शर्ती खालीलप्रमाणे..

- १) आपले दर संस्था /शॉप च्या लेटर हेडवरती असणे आवश्यक आहे.
- २) उपरोक्त दर हा GST व्यतिरीक्त Quote करावा.
- ३) आपले दरपत्रके दि.२३/०७/२०१८ पूर्वी कार्यालयात पोहच करावेत.
- ४) सदरचे दर हे फक्त अंदाजपत्रक बनविणेसाठी वापरण्यात येणार आहेत.

सही/---  
कार्यकारी अभियंता  
अभियांत्रिकी विभाग — ब